



NOTES

Solar panel installation as per manufacturers instructions.

Recommended solar fluid concentration 30-40%

Special care must be taken to ensure that the solar coil is free from air locks. This can take time and the best indication of a full system is when the solar pump is running quiet. Solar fluid must move freely to avoid panel overheating.

Recommended solar system cold pressure is 1.5bar

It is not recommended to run the solar system prior of filling of the boiler. This can lead to overheating of the solar system components.

JASPI UK www.jaspi.co.uk

Multifuel boilers
Solar thermal connection

DRAWN	VERSION	DATE	DRAWING REF.
SS		11.07.2011	Generic